No.	Items of work	Per	Quantity
8	Teakwood panelled windows with round iron bars, ½" thick with fittings complete, one shutter outside as per Margat's specifications.	S. ft.	162
9	Flooring with Cudappa slabs, 1½" thick over 3" concrete bed and cement painting.	100 S. ft.	630
10	Teakwood work, wrought and put up, with wood oiling	C. ft.	74
11	Roofing with 1st class Mangalore tiles over 2" x 1" teak reepers, nails, wood oiling, etc., complete	100 S. ft.	1,339
12	Ridge tiles set in mortar and 1" thick	R. ft.	106
13	Teakwood eave board, 9" deep with painting	"	140
14	Do finials do	Each	4
15	Chocolate painting	100 S. ft	716
16	Zinc sheets for valleys	S. ft.	32
17	Teakwood planks, ½" thick for valleys	"	32
18	Levelling ground, etc.	Lump sum Rs.	
	(7) Constructing a shop—		
1	Earthwork excavating foundation and filling in foundation and basement ..	100 C. ft,	841
2	Burnt brick in mortar	"	1,144
3	Do mud	"	1,222
4	Burnt stone slabs, 6" thick, one side dressed	S. ft.	167
5	Plastering with chunam	100 S. ft.	2,795
6	White and colourwashing	"	2,795
7	Teakwood panelled door, complete with fittings as per Margat's specifications ..	S. ft.	74
8	Do big doors with 1½" planks for shops with fittings ..	"	56
9	Do window panelled with ½" round iron bars, one shutter outside as per Margat's specifications.	"	48
10	Teakwood work, wrought and put up, with wood oiling	C. ft.	53
11	Roofing 1st class Mangalore tiles over 2" x 1" teak reepers, nails, wood oiling, etc., complete.	100 S. ft.	695
12	Ridge tiles set in mortar	R. ft.	29
13	Roofing with pucca terraced, complete	100 S. ft.	185
14	Brick masonry parapet wall including plastering and top cornice ..	R. ft.	29
15	Cornice, 9" complete	"	40
16	Chunam borders	"	32
17	Teakwood eave board, 9" deep and 1" thick, with painting	"	25
18	Chocolate painting, 2 coats	100 S. ft.	332
19	Levelling ground and clearing site	Lump sum Rs.	
	(8) Adding front verandah for Quarter Guards and Prisons—		
1	Dismantling and removing existing parapet wall	100 C. ft.	83
2	Preparing stone brackets and inserting into the wall	Each	4
3	Teakwood work, wrought and put up, with wood oiling	C. ft	50
4	Roofing with 1st class Mangalore tiles over 2" x 1" teak reepers nails, wood oiling, complete.	100 S. ft.	300
5	Ridge tiles set in mortar	R. ft.	14
6	Teakwood, 1" plank	S. ft.	72
7	Zinc sheet, 2' wide	"	72
8	Teakwood eave boards, 9" deep and 1" thick, with painting	R. ft.	60
9	Teakwood barge boards with finials and painting, complete	Each	2
10	Teakwood railings with painting	R. ft.	40
11	Removing and refixing doors and windows, masonry and plastering between the pillars of verandah.	Each	3
12	Chocolate painting	Lump sum Rs.	

K. V. KARVE,
Asst. Engineer,

CHITALDRUG DIVISION.

Abstract Notification.

The attention of the public is invited to the detail Notification published in pages 419 and 420 of the *Mysore Gazette* issue dated 21st July 1921, calling for tenders for Restoring the Hulemalali Minor Tank, Reg. No 143 of Holalkere Taluk.

Last date to receive tenders is 15th August 1921 and the earnest money to be deposited with tender is Rs. 100.

S. A RAMASWAMI IYER,
Executive Engineer.

MYSORE IRON WORKS, BHADRAVATI.

Dated 12th July 1921

Notice is hereby given that tenders will be received at the Office of the Executive Engineer, Mysore Iron Works, Bhadravati, up to 31st July 1921, for the supply of Iron Fittings and Glass panes to the Bungalows in the New Town at Bhadravati. An approximate list or quantities is enclosed. These quantities are not guaranteed. The supply should be completed by the end of September 1921.